MYSORE SPECIAL DIVISION.

Notice dated 24th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 20th February 1929, till 12 noon for extending the western wing of Government Branch Press at Mysore. An abstract of approximate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, State Loan Bonds at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money, and be superscribed "Tender for extending the western wing of Government Branch Press at Mysore" in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Superintending Engineer, Mysore Circle, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D. P. W. Specification.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

ABSTRACT.

No.	Items of work	Quantity		Per	Rate	Remarks
		North side	South side			
					Rs.	
1	Dismantling the existing building and removing the debris.	L. S.	L. S.			
2	Earthwork excavation for foundation and filling in basement watering and consolidating complete.	43	38	C.yds.		
3	Filling foundation with stone jelly concrete in chunam.	320	281	C.ft.		
4	Burnt brick in mortar filling foundation and basement.	1,253	1,118	,,		
5	Do superstructure pillars	472	415	,,		
6	Do do wall ...	1,750	1,594	,,		
7	Burnt stone slabs 3″ to 4″ thick 2 lines dressed and fixed.	389	444	S.ft.		
8	Teakwood wrought and put up ...	199·00	187·00	C.ft.		
9	Kind rod trusses as per design with T. W. Principal rafters 4½″ x 6″, tie rod 1″ diar struts 4½″ x 4½″, etc., complete.	7	6	Each		
10	Teakwood battened doors complete ...	56	56	S.ft.		
11	Teakwood windows (without shutter) iron bars, wire gauze, etc., complete.	221	205	,,		
12	Teakwood ventilators with glazed shutters complete.	84	74	,,		
13	Teakwood ornamental eaves board as per design.	201	175	R.ft.		

No.	Items of work	Quantity North side	Quantity South side	Per	Rate	Remarks
					Rs.	
14	Removing and refixing old eaves board to the gables including painting.	38	38	R.ft.		
15	Roofing with 1st class Mangalore pattern tiles on teak reepers complete.	8·00	6·37	Sqr.		
16	Mangalore ridge tiles set in mortar ...	70	57	R.ft.		
17	Roofing with 1st class Mangalore pattern tiles with teak reepers and ceiling tiles complete.	25·00	21·87	Sqr.		
18	Flooring with Kadappa slabs on 3" concrete bed and cement pointing complete.	4·32	3·74	,,		
19	Flooring with Mangalore square flooring tiles on 3" concrete lead and cement pointing.	16·00	14·16	,,		
20	Providing zinc gutters with brackets complete.	29	24	Each		
21	Plastering with chunam mortar ..	48·00	44·50	Sqr.		
22	White washing 2 coats	48·00	44·50	,,		
23	Chocolate painting 2 coats ...	7·21	6·00	,,		
24	Chunam borders	38	38	R.ft.		
25	Removing and refixing finials ...	1	1	Each		

V. V. KARVE,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 19th—21st January 1929.

The attention of the public is invited to the notice of calling tenders for improving the Government House (Deputy Commissioner's quarters) at Shimoga. *Vide* page 115-117, of the *Mysore Gazette*, dated 24th January 1929.

N. S. NARAYANSWAMY,
Executive Engineer.

KADUR DIVISION

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for constructing Police Lines at Basarikatte, Narasimharajapura Sub-Taluk, published in pages 85 and 86 of Part VI of *Mysore Gazette* dated 17th January 1929. The last date for receiving tender is 4th February 1929 till 2 P.M.

B. KRISHNA RAO,
Executive Engineer.

S. A. RAILWAY CONSTRUCTION DIVISION.

Abstract Notification dated 26th January 1929.

The attention of the public is invited to the Notification calling for tenders for Earth Work on S. A. Railway Construction, published on page 112, Part VI of the *Mysore Gazette*, dated 24th January 1929.

Last date for receiving tenders is 15th February 1929.

Y. K. RAMACHANDRA RAU,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE.

Notice No. Roc. 2455—*Sc.* 641 *of* 27-28, *dated 15th January* 1929.

Sealed tenders will be received in the office of the undersigned up to 12 noon, on Friday the 1st February 1929, for the supply of the spraying materials as detailed below required for the Mysore Agricultural Department.

For further particulars please see Part VI, page 89 of the *Mysore Gazette*, dated 17th January 1929.

LESLIE C. COLEMAN,
Director of Agriculture.